



CITY COUNCIL AGENDA ITEMS

To: Mayor Graham and City Council
From: Dennis Sullivan, Director of Engineering & Public Works
Walter Denton, City Administrator
Date: May 5, 2008
Subject: RESOLUTION – Lincoln Street Reconstruction – Phase 3

List of committees that have reviewed: None.

Background: The proposed improvement includes removal of existing roadway surfaces, concrete curb & gutters, storm sewers, catch basins, driveway pavement aprons, and concrete sidewalk; construction of a bituminous pavement on aggregate subgrade, temporary bituminous pavement on aggregate subgrade, storm sewers, inlets, concrete curb & gutters, driveway pavements (new concrete entrance aprons), concrete sidewalk (including construction of handicap accessible curb ramps), manhole adjustments, seeding; and all appurtenant construction, thereto. The project site is approximately 650 L.F. and is located on North Lincoln Avenue from just south of Monroe Street to just north of East Jackson Street (see attached).

The period of performance for this work will be approximately 60 days beginning approximately June 1, 2008. The majority of the work is expected to be completed when schools are not in session to minimize disruption of traffic during peak periods. This section of road will be closed to through traffic with access to the residents only as required.

Veile Construction, the low bidder, was the contractor for the construction of Seven Hills Road from Hwy 50 to the railroad bridge near State Street.

Legal Considerations, if any: Normal contract execution concerns.

Budget Impact: This item is a late addition to the City's FY09 Proposition S Budget due to the deterioration of the roadway during the late winter freeze-thaw cycles.

Staff recommendation: Staff recommends contracting with Veile Construction for the reconstruction of Lincoln Street, Phase 3 in an amount based on unit prices for a total of \$263,696.00.