

WATER LATERAL INSTALLATION

- SHOULD HAVE “L” OR “K” COPPER OR 200 PSI PLASTIC WATER LINE TO BE CONNECTED TO THE METER PIT.
- SERVICE LINE SHOULD BE WITHIN 10-12 FEET FROM BACK OF CURB AND THE LINE 36” DEEP FROM GRADE OF YARD.
- A SHUT OFF VALVE MUST BE INSTALLED ON THE CUSTOMER’S SIDE OF THE METER.
- THE SERVICE LINE NEEDS TO BE RUN OUT TO THE MIDDLE OF THE YARD. IF THE HOUSE SITS ON A CORNER LOT CONTACT THE OPERATIONS GROUP WITH ANY QUESTIONS.

AFTER SERVICE LINE AND VALVE ARE INSTALLED, CONTACT PUBLIC WORKS OPERATIONS GROUP AT 624-4500, Ext. 5 TO SCHEDULE A WATER TAP - ALLOW 3 WEEKS FOR COMPLETION

**City of O'Fallon Public Works Operations Group
255 S Lincoln Ave
O'Fallon, IL 62269**